State of Nevada Department of Conservation and Natural Resources Division of State Parks Facility Condition Analysis

ECHO CANYON STATE PARK

HC 74, Box 295 Pioche, Nevada 89043

Site Number: 9945 STATE OF NEVADA PUBLIC WORKS DIVISION FACILITY CONDITION ANALYSIS



Report distributed in April 2017

State of Nevada Department of Conservation and Natural Resources Division of State Parks Facility Condition Analysis

The Facility Condition Analysis Program was created under the authority found in NRS 341.128. The State Public Works Division develops this report using cost estimates based on contractor pricing which includes materials, labor, location factors and profit and overhead. The costs of project design, management, special testing and inspections, inflation and permitting fees are not included. Cost estimates are derived from the R.S. Means Cost Estimating Guide and from comparable construction costs of projects completed by SPWD project managers.

The deficiencies outlined in this report were noted from a visual survey. This report does not address routine maintenance needs. Recommended projects do not include telecommunications, furniture, window treatments, space change, program issues, or costs that could not be identified or determined from the survey and available building information. If there are buildings without projects listed, this indicates that only routine maintenance needs were found. This report considers probable facility needs for a 10 year planning cycle.

This report is not a guarantee of funding and should not be used for budgeting purposes. This report is a planning level document for agencies and the State Public Works Division to assess the needs of the Building and/or Site and to help support future requests for ADA upgrades / renovations, Capital Improvement Projects and maintenance. The final scope and estimate of any budget request should be developed by a qualified individual. Actual project costs will vary from those proposed in this report when the final scope and budget are developed.

Establishing a Facility Condition Needs Index (FCNI) for each building

The FCA reports identify maintenance items and establish construction cost estimates. These costs are summarized at the end of the report and noted as construction costs per square foot. A FCNI is commonly used by facility managers to make a judgment whether to recommend whole replacement of facilities, rather than expending resources on major repairs and improvements. The FCNI is a ratio between the proposed facility upgrade costs and facility replacement costs (FRC). Those buildings with indices greater than .50 or 50% are recommended to be considered for complete replacement.

Class Definitions

PRIORITY CLASS 1 - Currently Critical (Immediate to Two Years)

Projects in this category require immediate action to return a facility to normal operation, stop accelerated deterioration, correct a fire/life safety hazard, or correct an ADA requirement.

PRIORITY CLASS 2 - Necessary - Not Yet Critical (Two to Four Years)

Projects in this category include conditions requiring appropriate attention to preclude predictable deterioration or potential downtime and the associated damage or higher costs if deferred further.

PRIORITY CLASS 3 - (Four to Ten Years)

Projects in this category include items that represent a sensible improvement to existing conditions. These items are not required for the most basic function of a facility; however, Priority 3 projects will either improve overall usability and/or reduce long-term maintenance.

	ber: 9945 Building Name	Facility Condition Nee		-	Survey Date	Cost to Repair: P1	Cost to Repair: P2	Cost to Repair: P3	Total Cost to Repair	Cost to Replace	FCNI
				·							
0508	PARK OFFICE		147	1986	4/13/2016	\$33,000	\$5,940	\$0	\$38,940	\$29,400	132%
	HC 74 Box 295, Pioche	Echo Canyon		1000		*	*~ 000	¢100	AZ 100	* 1 7 00	1150
3727	PARK RESIDENCE MET		90	1990	4/13/2016	\$0	\$5,000	\$180	\$5,180	\$4,500	115%
	HC 74 Box 295, Pioche	Echo Canyon									
1068	RAMADA - GROUP AR		493	1990	4/13/2016	\$0	\$20,000	\$0	\$20,000	\$25,000	80%
	HC 74 Box 295, Pioche	Echo Canyon									
1067	ADA RAMADA - GROU		493	1990	4/13/2016	\$0	\$20,000	\$0	\$20,000	\$25,000	80%
	HC 74 Box 295, Pioche	Echo Canyon									
0510	FISH CLEANING STATI		93	1990	4/13/2016	\$12,500	\$1,860	\$0	\$14,360	\$23,250	62%
	HC 74 Box 295, Pioche	Echo Canyon									
1064	COMFORT STATION #1	- NORTH CAMPGROUND	433	1990	4/13/2016	\$72,500	\$4,330	\$4,330	\$81,160	\$173,200	47%
	HC 74 Box 295, Pioche	Echo Canyon									
1063	COMFORT STATION #2	- GROUP AREA	437	1990	4/13/2016	\$72,500	\$4,370	\$4,370	\$81,240	\$174,800	46%
	HC 74 Box 295, Pioche	Echo Canyon									
3081	PARK OFFICE STORAG	E SHED #1	288	2008	4/13/2016	\$0	\$2,880	\$3,456	\$6,336	\$14,400	44%
	HC 74 Box 295, Pioche	Echo Canyon									
3082	PARK OFFICE STORAG	E SHED #2	288	2004	4/13/2016	\$0	\$6,336	\$0	\$6,336	\$14,400	44%
	HC 74 Box 295, Pioche	Echo Canyon									
1065	PARK WELL HOUSE		48	1970	4/13/2016	\$5,280	\$960	\$0	\$6,240	\$15,000	42%
	HC 74 Box 295, Pioche	Echo Canyon									
0509	COMFORT STATION #3	- BOAT RAMP	250	1994	4/13/2016	\$6,500	\$17,000	\$2,500	\$26,000	\$100,000	26%
	HC 74 Box 295, Pioche	Echo Canyon									
0507	PARK RESIDENCE		1580	1991	4/13/2016	\$2,500	\$0	\$31,600	\$34,100	\$474,000	7%
	HC 74 Box 295, Pioche	Echo Canyon									
3728	PARK RESIDENCE MET	TAL SHED #2	450	0	4/13/2016	\$0	\$0	\$900	\$900	\$22,500	4%
	HC 74 Box 295, Pioche	Echo Canyon									
1101	PARK OFFICE STORAGE	E SHED #3	198	1990	4/13/2016	\$0	\$396	\$0	\$396	\$9,900	4%
	HC 74 Box 295, Pioche	Echo Canyon									
3750	PARK OFFICE SHADE S	STRUCTURE	232	1990	4/13/2016	\$0	\$464	\$0	\$464	\$11,600	4%
	HC 74 Box 295, Pioche	Echo Canyon									
3729	RV ADA COMFORT STA	ATION #1	432	2014	4/13/2016	\$0	\$0	\$8,640	\$8,640	\$216,000	4%
	HC 74 Box 295, Pioche	Echo Canyon									

Site num		acility Condition Nee		•		Cost to	Cost to	Cost to	Total Cost	Cost to	
Index #	Building Name		Sq. Feet	Yr. Built	Survey Date	Repair: P1	Repair: P2	Repair: P3	to Repair	Replace	FCN
9945	ECHO CANYON STATE PAR	RK SITE		1970	4/13/2016	\$50,000	\$71,924	\$0	\$121,924	\$0	0%
	HC 74 Box 295, Pioche	Echo Canyon									
1084	RAMADA #16 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1083	RAMADA #15 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1082	RAMADA #14 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1081	RAMADA #13 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1085	RAMADA #17 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1076	RAMADA #08 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1087	RAMADA #19 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1088	RAMADA #20 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1086	RAMADA #18 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1080	RAMADA #12 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1079	RAMADA #11 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1089	RAMADA #21 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1077	RAMADA #09 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1095	RAMADA #27 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1075	RAMADA #07 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1074	RAMADA #06 - CAMPGROU	ND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									

Site num	ber: 9945	Facility Condition Nee		-		Cost to	Cost to	Cost to	Total Cost	Cost to	
Index #	Building Name		Sq. Feet	Yr. Built	Survey Date	Repair: P1	Repair: P2	Repair: P3	to Repair	Replace	FCN
1073	RAMADA #05 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1072	RAMADA #04 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1071	RAMADA #03 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1070	RAMADA #02 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1069	RAMADA #01 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
0512	RAMADA #34 - PICNIC		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
0511	RAMADA #33 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1078	RAMADA #10 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
3743	RAMADA #50 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
1093	RAMADA #25 - CAMPGRO	OUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
3737	RAMADA #44 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3738	RAMADA #45 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3739	RAMADA #46 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3740	RAMADA #47 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3735	RAMADA #42 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3742	RAMADA #49 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3734	RAMADA #41 - CAMPGRO	OUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									

Site num	ber: 9945 Facil	lity Condition Nee		-		Cost to	Cost to	Cost to	Total Cost	Cost to	
Index #	Building Name		Sq. Feet	Yr. Built	Survey Date	Repair: P1	Repair: P2	Repair: P3	to Repair	Replace	FCN
3744	RAMADA #51 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3745	RAMADA #52 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3746	RAMADA #53 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3747	RAMADA #54 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3748	RAMADA #55 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3749	RAMADA #56 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3741	RAMADA #48 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
1100	RAMADA #32 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1091	RAMADA #23 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1092	RAMADA #24 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1094	RAMADA #26 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1096	RAMADA #28 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1097	RAMADA #29 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
3736	RAMADA #43 - CAMPGROUND		256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
1099	RAMADA #31 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
1090	RAMADA #22 - CAMPGROUND		224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
3083	RAMADA #35 - SOUTH PICNIC #	AREA	144	2008	4/13/2016	\$0	\$0	\$0		\$7,200	
	HC 74 Box 295, Pioche	Echo Canyon									

Site num	ber: 9945	Facility Condition Net	eds Index I	Report		Cost to	Cost to	Cost to	Total Cost	Cost to	
Index #	Building Name	_	Sq. Feet	Yr. Built	Survey Date	Repair: P1	Repair: P2	Repair: P3	to Repair	Replace	FCNI
3084	RAMADA #36 - SOUTH	PICNIC AREA	144	2008	4/13/2016	\$0	\$0	\$0		\$7,200	
	HC 74 Box 295, Pioche	Echo Canyon									
3730	ADA RAMADA #37 - CA	AMPGROUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3731	ADA RAMADA #38 - CA	AMPGROUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3732	RAMADA #39 - CAMPG	GROUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
3733	RAMADA #40 - CAMPG	ROUND	256	2009	4/13/2016	\$0	\$0	\$0		\$12,800	
	HC 74 Box 295, Pioche	Echo Canyon									
1098	RAMADA #30 - CAMPG	GROUND	224	1990	4/13/2016	\$0	\$0	\$0		\$11,200	
	HC 74 Box 295, Pioche	Echo Canyon									
		Report Totals:	18,970	5		\$254,780	\$161,460	\$55,976	\$472,216	\$1,984,150	24%

Table of Contents

Building Name	Index #	
ECHO CANYON STATE PARK SITE	9945	
PARK OFFICE SHADE STRUCTURE	3750	
RAMADA #56 - CAMPGROUND	3749	No Current Projects
RAMADA #55 - CAMPGROUND	3748	No Current Projects
RAMADA #54 - CAMPGROUND	3747	No Current Projects
RAMADA #53 - CAMPGROUND	3746	No Current Projects
RAMADA #52 - CAMPGROUND	3745	No Current Projects
RAMADA #51 - CAMPGROUND	3744	No Current Projects
RAMADA #50 - CAMPGROUND	3743	No Current Projects
RAMADA #49 - CAMPGROUND	3742	No Current Projects
RAMADA #48 - CAMPGROUND	3741	No Current Projects
RAMADA #47 - CAMPGROUND	3740	No Current Projects
RAMADA #46 - CAMPGROUND	3739	No Current Projects
RAMADA #45 - CAMPGROUND	3738	No Current Projects
RAMADA #44 - CAMPGROUND	3737	No Current Projects
RAMADA #43 - CAMPGROUND	3736	No Current Projects
RAMADA #42 - CAMPGROUND	3735	No Current Projects
RAMADA #41 - CAMPGROUND	3734	No Current Projects
RAMADA #40 - CAMPGROUND	3733	No Current Projects
RAMADA #39 - CAMPGROUND	3732	No Current Projects
ADA RAMADA #38 - CAMPGROUND	3731	No Current Projects
ADA RAMADA #37 - CAMPGROUND	3730	No Current Projects
RV ADA COMFORT STATION #1	3729	
PARK RESIDENCE METAL SHED #2	3728	
PARK RESIDENCE METAL SHED #1	3727	
RAMADA #36 - SOUTH PICNIC AREA	3084	No Current Projects
RAMADA #35 - SOUTH PICNIC AREA	3083	No Current Projects
PARK OFFICE STORAGE SHED #2	3082	
PARK OFFICE STORAGE SHED #1	3081	
PARK OFFICE STORAGE SHED #3	1101	
RAMADA #32 - CAMPGROUND	1100	No Current Projects
RAMADA #31 - CAMPGROUND	1099	No Current Projects
RAMADA #30 - CAMPGROUND	1098	No Current Projects

RAMADA #29 - CAMPGROUND	1097	No Current Projects
RAMADA #28 - CAMPGROUND	1096	No Current Projects
RAMADA #27 - CAMPGROUND	1095	No Current Projects
RAMADA #26 - CAMPGROUND	1094	No Current Projects
RAMADA #25 - CAMPGROUND	1093	No Current Projects
RAMADA #24 - CAMPGROUND	1092	No Current Projects
RAMADA #23 - CAMPGROUND	1091	No Current Projects
RAMADA #22 - CAMPGROUND	1090	No Current Projects
RAMADA #21 - CAMPGROUND	1089	No Current Projects
RAMADA #20 - CAMPGROUND	1088	No Current Projects
RAMADA #19 - CAMPGROUND	1087	No Current Projects
RAMADA #18 - CAMPGROUND	1086	No Current Projects
RAMADA #17 - CAMPGROUND	1085	No Current Projects
RAMADA #16 - CAMPGROUND	1084	No Current Projects
RAMADA #15 - CAMPGROUND	1083	No Current Projects
RAMADA #14 - CAMPGROUND	1082	No Current Projects
RAMADA #13 - CAMPGROUND	1081	No Current Projects
RAMADA #12 - CAMPGROUND	1080	No Current Projects
RAMADA #11 - CAMPGROUND	1079	No Current Projects
RAMADA #10 - CAMPGROUND	1078	No Current Projects
RAMADA #09 - CAMPGROUND	1077	No Current Projects
RAMADA #08 - CAMPGROUND	1076	No Current Projects
RAMADA #07 - CAMPGROUND	1075	No Current Projects
RAMADA #06 - CAMPGROUND	1074	No Current Projects
RAMADA #05 - CAMPGROUND	1073	No Current Projects
RAMADA #04 - CAMPGROUND	1072	No Current Projects
RAMADA #03 - CAMPGROUND	1071	No Current Projects
RAMADA #02 - CAMPGROUND	1070	No Current Projects
RAMADA #01 - CAMPGROUND	1069	No Current Projects
RAMADA - GROUP AREA	1068	
ADA RAMADA - GROUP AREA	1067	
PARK WELL HOUSE	1065	
COMFORT STATION #1 - NORTH CAMPGROUND	1064	
COMFORT STATION #2 - GROUP AREA	1063	
RAMADA #34 - PICNIC	0512	No Current Projects
RAMADA #33 - CAMPGROUND	0511	No Current Projects
FISH CLEANING STATION - BOAT RAMP	0510	
COMFORT STATION #3 - BOAT RAMP	0509	

PARK OFFICE0508PARK RESIDENCE0507

ECHO CANYON STATE PARK SITE BUILDING REPORT

The Echo Canyon State Park Site offers a 65-acre reservoir with a campground, picnic area, group use facilities and a boat launch. The park is popular for camping, fishing, hiking and enjoying the beautiful scenery of eastern Nevada. Abundant wildlife, a wide variety of native plants and unique rock formations make exploration a favorite activity. Echo Canyon is located 12 miles east of Pioche via State Routes 322 and 323. The park's elevation is 5,200' and although it is open year-round, visitors should be aware of occasional snow during winter months. Echo Canyon State Park is one of five state parks located in Lincoln County. The site has a well located below the dam that pumps water to a 40,000 gallon underground storage tank above the north campground where the water is gravity fed to the site. The park encompasses 1,280 acres.

PRIORITY CLASS 1 PROJECTS	5 Total Construction Cost for Priority 1 Projects:	\$50,000
Currently Critical	Immediate to Two Years	

ADA ACCESSIBLE PATH OF TRAVEL

The Americans with Disabilities Act (ADA) provides for accessibility to sites and services for people with physical limitations. A concrete parking area, passenger loading area and path of travel to the Park Office are necessary to comply with ADA accessibility requirements. This project would provide for a concrete, van accessible, ADA parking and loading space, and a concrete ADA walkway to the existing sidewalk. This will require re-grading, placement of P.C. concrete, signage, striping and any other necessary upgrades. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180, and the most current version of the ADA Standards for Accessible Design were used as references for this project. 750 square feet of concrete was used for this estimate. It is recommended that this project coincide with the ADA parking and ADA signage projects.

ADA HANDRAIL INSTALLATION

The Americans with Disabilities Act (ADA) ramp leading up to the amphitheater is missing handrails. This project recommends the installation of handrails on both sides of the ramp and compliant returns and supports. Nevada Revised Statutes (NRS) 338.180, 2012 International Building Code (IBC) Chapter 10, Section 1012, ICC/ANSI A117.1 - 2009, and the most current version of the Americans with Disabilities Act Accessible Guidelines (ADAAG) were used as references for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

ADA PARKING SPACE

The Americans with Disabilities Act (ADA) provides for accessibility to sites and services for people with physical limitations. At the Park Office a concrete parking area and passenger loading area are necessary to comply with ADA requirements. This project would provide for a concrete, van accessible, ADA parking and loading space and walkway to the existing sidewalk. This will require regrading, installing P.C. concrete, striping, signage and any other necessary upgrades. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the

most current version of the ADA Standards for Accessible Design were used as references for this project. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Project Index #: 9945ADA3 Construction Cost \$15,000

Project Index #:

Construction Cost

Construction Cost\$15,000ng handrails. This project

Project Index #: 9945ADA5 Construction Cost \$2,500

9945ADA6

\$30,000

ADA SIGNAGE

The Americans with Disabilities Act (ADA) provides for accessibility to sites and services for people with physical limitations. The criteria includes: sign mounting heights and locations; character heights and proportions; raised and Braille characters/pictograms; and sign contrast and finish. The signage at the Park Office does not comply with these criteria. This project would provide funding for the purchase and installation of ADA signage, including directional signage from parking to accessible building entrances. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the most current version of the ADA Standards For Accessible Design were used as references for this project.

PRIORITY CLASS 2 PROJECTS

Necessary - Not Yet Critical Two to Four Years

EXTERIOR FINISHES

Project Index #:9945EXT1Construction Cost\$71,924

\$71,924

Total Construction Cost for Priority 2 Projects:

There are 63 wood and steel shade ramadas in different locations throughout the site which are either 144 s.f., 224 s.f., 234 s.f., 256 s.f., or 493 s.f. for a total of 14,010 square feet. It is important to maintain the finish, weather resistance and appearance of the structures. This project would provide for the painting of the structures. It is recommended that this project be scheduled on a cyclical basis to maintain the integrity of the structures.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

Priority Class 1:	\$50,000
Priority Class 2:	\$71,924
Priority Class 3:	\$0
Grand Total:	\$121,924

Project Index #:9945ADA7Construction Cost\$2,500ces for people with physical

State of Nevada / Conservation & Natural Resources PARK OFFICE SHADE STRUCTURE SPWD Facility Condition Analysis - 3750 **Survey Date:** 4/13/2016

PARK OFFICE SHADE STRUCTURE **BUILDING REPORT**

The Park Office Shade Structure is located in the area of the Park Office. It is a wood post and beam structure with a metal roof.

PRIORITY CLASS 2 PROJECTS

Two to Four Years Necessary - Not Yet Critical

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the ramada. This project would provide funding to protect the exterior of the ramada excluding the roof. Included in the cost is power washing and staining the wood. It is recommended that the ramada be stained in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

BUILDING INFORMATION:

Gross Area (square feet):	232			
Year Constructed:	1990			
Exterior Finish 1:	100 #		Wood Post	/ Open
Exterior Finish 2:	0	#		
Number of Levels (Floors):	1		Basement?	No
IBC Occupancy Type 1:	100	#	U	
IBC Occupancy Type 2:	0	#		
Construction Type:	Wood post and beam			
IBC Construction Type:	V-B			
Percent Fire Suppressed:	0	#		

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$2.00	Project Construction Cost per Square Foot:	\$0	Priority Class 1:
\$12,000	Total Facility Replacement Construction Cost:	\$464	Priority Class 2:
\$50	Facility Replacement Cost per Square Foot:	\$0	Priority Class 3:
4%	FCNI:	\$464	Grand Total:

Site number: 9945

\$464

3750EXT1 **Project Index #: Construction Cost** \$464

Total Construction Cost for Priority 2 Projects:

State of Nevada / Conservation & Natural Resources **RV ADA COMFORT STATION #1** SPWD Facility Condition Analysis - 3729 Survey Date: 4/13/2016

RV ADA COMFORT STATION #1 BUILDING REPORT

The RV ADA Comfort Station #1 is a concrete masonry and steel framed structure on a concrete slab-on-grade foundation with a standing seam metal roof. There are four restrooms and two shower rooms for park visitors located in the RV campground at Echo Canyon State Park. The building is heated by hydronic/ radiant floor heating for year-round use.

PRIORITY CLASS 3 PROJECT	S Total Construction Cost for Priority 3 Projects: \$8	,640
Long-Term Needs	Four to Ten Years	

EXTERIOR/INTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the interior and exterior of the building. Included in the cost are cleaning and sealing the precast concrete and caulking of the windows, flashing, fixtures and all other penetrations. An epoxy paint is recommended on the interior precast concrete. It is recommended that the building be sealed and caulked in the next 4-5 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

BUILDING INFORMATION:

Gross Area (square feet):	432	2
Year Constructed:	201	14
Exterior Finish 1:	30	# Painted CMU
Exterior Finish 2:	70	# Painted Stucco / EIFS
Number of Levels (Floors):	1	Basement? No
IBC Occupancy Type 1:	100	0 # U
IBC Occupancy Type 2:	0	#
Construction Type:	Con	ncrete masonry and steel framed
IBC Construction Type:	V-B	В
Percent Fire Suppressed:	0	#

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$20.00	Project Construction Cost per Square Foot:	\$0	Priority Class 1:
\$216,000	Total Facility Replacement Construction Cost:	\$0	Priority Class 2:
\$500	Facility Replacement Cost per Square Foot:	\$8,640	Priority Class 3:
4%	FCNI:	\$8,640	Grand Total:

Site number: 9945

Project Index #: 3729EXT1 \$8,640

State of Nevada / Conservation & Natural Resources PARK RESIDENCE METAL SHED #2 SPWD Facility Condition Analysis - 3728 Survey Date: 4/13/2016

PARK RESIDENCE METAL SHED #2

BUILDING REPORT

The Park Residence Metal Shed #2 is constructed of a portable metal frame on a concrete slab-on-grade foundation with metal siding and a metal roof. It is located adjacent to the Park Residence.

PRIORITY CLASS 3 PROJECT	S Total Construction Cost for Priority 3 Projects:	\$900
Long-Term Needs	Four to Ten Years	

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is caulking and sealing of the windows, flashing, fixtures and all other penetrations. It is recommended that the building be caulked and sealed in the next 4-5 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

BUILDING INFORMATION:

Gross Area (square feet):	450			
Year Constructed:	0			
Exterior Finish 1:	0	#		
Exterior Finish 2:	0	#		
Number of Levels (Floors):	0		Basement?	No
IBC Occupancy Type 1:	0	#		
IBC Occupancy Type 2:	0	#		
Construction Type:				
IBC Construction Type:				

Percent Fire Suppressed: 0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$2.00	Project Construction Cost per Square Foot:	\$0	Priority Class 1:
\$22,000	Total Facility Replacement Construction Cost:	\$0	Priority Class 2:
\$50	Facility Replacement Cost per Square Foot:	\$900	Priority Class 3:
4%	FCNI:	\$900	Grand Total:

Site number: 9945

Project Index #: 3728EXT1 Construction Cost \$900 State of Nevada / Conservation & Natural ResourcesPARK RESIDENCE METAL SHED #1SPWD Facility Condition Analysis - 3727Survey Date:4/13/2016

PARK RESIDENCE METAL SHED #1

BUILDING REPORT

The Park Residence Metal Shed #1 is constructed of a portable metal frame on a concrete slab-on-grade foundation with metal siding and a metal roof. It is located adjacent to the Park Residence.

PRIORITY CLASS 2 PROJECT	5 Total Construction Cost for Priority 2 Projects:	\$5,000
Necessary - Not Yet Critical	Two to Four Years	

SAFETY CABINETS

The building contains many different paints, stains, and other hazardous products located on open shelves and on the floor. This does not meet Occupational Safety and Health Administration (OSHA) standards or International Fire Code (IFC) for hazardous materials containment. This project would provide for a self-closing hazardous storage container in the building and the installation of placards on the building's exterior in accordance with OSHA 1910.106 (d) and IFC Chapter 57 Section 5704.3.2.1.3.

PRIORITY CLASS 3 PROJECTS	S Total Construction Cost for Priority 3 Projects:	
Long-Term Needs	Four to Ten Years	

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is caulking and sealing of the flashing, fixtures and all other penetrations. It is recommended that the building be caulked and sealed in the next 4-5 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

BUILDING INFORMATION:

Gross Area (square feet):	90			
Year Constructed:	199	0		
Exterior Finish 1:	0	#		
Exterior Finish 2:	0	#		
Number of Levels (Floors):	0		Basement?	No
IBC Occupancy Type 1:	0	#		
IBC Occupancy Type 2:	0	#		
Construction Type:				
IBC Construction Type:				
Percent Fire Suppressed:	0	#		

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$57.56	Project Construction Cost per Square Foot:	\$0	Priority Class 1:
\$4,000	Total Facility Replacement Construction Cost:	\$5,000	Priority Class 2:
\$50	Facility Replacement Cost per Square Foot:	\$180	Priority Class 3:
130%	FCNI:	\$5,180	Grand Total:

Site number: 9945

3727SFT1

3727EXT1

\$180

\$5,000

Project Index #:

Construction Cost

Project Index #:

State of Nevada / Conservation & Natural ResourcesPARK OFFICE STORAGE SHED #2SPWD Facility Condition Analysis - 3082Survey Date:4/13/2016

PARK OFFICE STORAGE SHED #2

BUILDING REPORT

The Park Office Storage Shed #2 is a portable wood framed structure on a concrete slab-on-grade foundation with a gambrel style asphalt composition roof. It is located adjacent to the Park Office below the dam.

PRIORITY CLASS 2 PROJECT	Total Construction Cost for Priority 2 Projects:	\$6,336
Necessary - Not Yet Critical	Two to Four Years	

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding, priming and painting and caulking of the flashing, fixtures and all other penetrations. It is recommended that the building be painted in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

ROOF REPLACEMENT

The asphalt composition shingle roof on this building was in poor condition at the time of the survey. It is recommended that this building be re-roofed in the next 2-3 years with a new 50 year asphalt composition roofing shingle and new underlayment. This estimate includes the installation of a new roof and the removal and disposal of the old roofing.

BUILDING INFORMATION:

Gross Area (square feet):	288
Year Constructed:	2004
Exterior Finish 1:	100 # Painted Wood Siding
Exterior Finish 2:	0 #
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # S-2
IBC Occupancy Type 2:	0 #
Construction Type:	Portable Wood Shed
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$22.00	Project Construction Cost per Square Foot:	\$0	Priority Class 1:
\$14,000	Total Facility Replacement Construction Cost:	\$6,336	Priority Class 2:
\$50	Facility Replacement Cost per Square Foot:	\$0	Priority Class 3:
45%	FCNI:	\$6,336	Grand Total:

Site number: 9945

3082EXT1

3082EXT2

\$3,456

\$2,880

Project Index #:

Project Index #:

Construction Cost

State of Nevada / Conservation & Natural ResourcesPARK OFFICE STORAGE SHED #1SPWD Facility Condition Analysis - 3081Survey Date:4/13/2016

PARK OFFICE STORAGE SHED #1

BUILDING REPORT

The Park Office Storage Shed #1 is a portable wood framed structure on a concrete slab-on-grade foundation with a gambrel style asphalt composition roof. It is located adjacent to the Park Office below the dam.

PRIORITY CLASS 2 PROJECT	S Total Construction Cost for Priority 2 Projects:	\$2,880
Necessary - Not Yet Critical	Two to Four Years	

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding, priming and painting and caulking of the flashing, fixtures and all other penetrations. It is recommended that the building be painted in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

PRIORITY CLASS 3 PROJECTS	Total Construction Cost for Priority 3 Projects:	\$3,456

Long-Term Needs

```
Four to Ten Years
```

Project Index #: 3081EXT2 Construction Cost \$3,456

Project Index #:

Construction Cost

The asphalt composition shingle roof on this building was in poor condition at the time of the survey. It is recommended that this building be re-roofed in the next 4-5 years with a new 50 year asphalt composition roofing shingle and new underlayment. This estimate includes the installation of a new roof and the removal and disposal of the old roofing.

BUILDING INFORMATION:

ROOF REPLACEMENT

Gross Area (square feet):	288
Year Constructed:	2008
Exterior Finish 1:	100 # Painted Wood Siding
Exterior Finish 2:	0 #
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # S-2
IBC Occupancy Type 2:	0 #
Construction Type:	Portable Wood Shed
IBC Construction Type:	V-B

Percent Fire Suppressed: 0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$22.00	Project Construction Cost per Square Foot:	\$0	Priority Class 1:
\$14,000	Total Facility Replacement Construction Cost:	\$2,880	Priority Class 2:
\$50	Facility Replacement Cost per Square Foot:	\$3,456	Priority Class 3:
45%	FCNI:	\$6,336	Grand Total:

Site number: 9945

3081EXT1

\$2,880

State of Nevada / Conservation & Natural ResourcesPARK OFFICE STORAGE SHED #3SPWD Facility Condition Analysis - 1101Survey Date:4/13/2016

PARK OFFICE STORAGE SHED #3

BUILDING REPORT

The Park Office Storage Shed #3 is a portable metal shed on a concrete slab-on-grade foundation. It is located adjacent to the Park Office below the dam.

PRIORITY CLASS 2 PROJECTS

Total Construction Cost for Priority 2 Projects:\$396

Necessary - Not Yet Critical Two to Four Years

EXTERIOR FINISHES

Project Index #: 1101EXT1 Construction Cost \$396

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is caulking and sealing the flashing, fixtures and all other penetrations. It is recommended that the building be caulked and sealed in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

BUILDING INFORMATION:

Gross Area (square feet):	198
Year Constructed:	1990
Exterior Finish 1:	100 # Metal Siding
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # S-2
IBC Occupancy Type 2:	#
Construction Type:	Portable Metal Building
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

Priority Class 1:	\$0	Project Construction Cost per Square Foot:	\$2.00
Priority Class 2:	\$396	Total Facility Replacement Construction Cost:	\$10,000
Priority Class 3:	\$0	Facility Replacement Cost per Square Foot:	\$50
Grand Total:	\$396	FCNI:	4%

Site number: 9945

State of Nevada / Conservation & Natural Resources **RAMADA - GROUP AREA** SPWD Facility Condition Analysis - 1068 Survey Date: 4/13/2016

RAMADA - GROUP AREA

The Ramada is a wood post and beam structure with a metal roofing system. The Ramada is located in the group use area on the south side of the reservoir.

PRIORITY CLASS 2 PROJECTS

Two to Four Years Necessary - Not Yet Critical

REBUILD STRUCTURE

BUILDING REPORT

Total Construction Cost for Priority 2 Projects: \$20,000

1068EXT1 **Construction Cost** \$20,000

The ramada is structurally failing and should be scheduled for replacement. This project would provide for demolishing the existing structure and rebuilding a new one. The new structure will have new concrete footings, steel framing and a metal standing seam roof. The design plans and permitting fees are not included in this estimate.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

BUILDING INFORMATION:

Gross Area (square feet):	493
Year Constructed:	1990
Exterior Finish 1:	100 # Wood Post & Beam/
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # U
IBC Occupancy Type 2:	#
Construction Type:	Wood Post & Beam
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

Priority Class 1:	\$0	Project Construction Cost per Square Foot:	\$40.57
Priority Class 2:	\$20,000	Total Facility Replacement Construction Cost:	\$25,000
Priority Class 3:	\$0	Facility Replacement Cost per Square Foot:	\$51
Grand Total:	\$20,000	FCNI:	80%

Project Index #:

Site number: 9945

State of Nevada / Conservation & Natural ResourcesADA RAMADA - GROUP AREASPWD Facility Condition Analysis - 1067Survey Date:4/13/2016

ADA RAMADA - GROUP AREA

BUILDING REPORT

The ADA Ramada is a wood post and beam structure with a metal roofing system. This Ramada is located in the group use area on the south side of the reservoir. This Ramada has an ADA accessible route from a parking space to the facility.

PRIORITY CLASS 2 PROJECTS

Total Construction Cost for Priority 2 Projects:

Necessary - Not Yet Critical Two to Four Years

REBUILD STRUCTURE

Project Index #:1067EXT1Construction Cost\$20,000

The ramada is structurally failing and should be scheduled for replacement. This project would provide for demolishing the existing structure and rebuilding a new one. The new structure will have new concrete footings, steel framing and a metal standing seam roof. The design plans and permitting fees are not included in this estimate.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

BUILDING INFORMATION:

Gross Area (square feet):	493			
Year Constructed:	199()		
Exterior Finish 1:	100	#	Wood Post & B	eam/
Exterior Finish 2:		#		
Number of Levels (Floors):	1		Basement? No	
IBC Occupancy Type 1:	100	#	U	
IBC Occupancy Type 2:		#		
Construction Type:	Woo	d I	Post & Beam	
IBC Construction Type:	V-B			
Percent Fire Suppressed:	0	#		

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

Priority Class 1:	\$0	Project Construction Cost per Square Foot:	\$40.57
Priority Class 2:	\$20,000	Total Facility Replacement Construction Cost:	\$25,000
Priority Class 3:	\$0	Facility Replacement Cost per Square Foot:	\$51
Grand Total:	\$20,000	FCNI:	80%

Site number: 9945

\$20,000

State of Nevada / Conservation & Natural Resources PARK WELL HOUSE SPWD Facility Condition Analysis - 1065 Survey Date: 4/13/2016

PARK WELL HOUSE

BUILDING REPORT

The Park Well House is a precast concrete structure on a concrete slab-on-grade foundation. The well head and pumping system is located in this building and is the primary source of potable water for the park.

PRIORITY CLASS 1 PROJECT	5 Total Construction Cost for Priority 1 Projects:	\$5,280
Currently Critical	Immediate to Two Years	

CONCRETE PATCH/ ROOFING

It is important to maintain the water proofing and structural integrity of the concrete roof deck on the building. This project would provide funding to repair the spalling concrete using an epoxy patch (to repair and seal) and then painting with an epoxy-based paint on the concrete roof decking. Included in the cost is the preparation of the concrete roof decking by cleaning, sanding, and removing all paint, loose concrete and aggregate from the roof decking. Per 2012 International Energy Conservation Code (IECC), the minimum insulation in a zone 5 entirely above the deck per Table C402.2 is R-25. After the concrete roof decking is completely repaired, an R-25 insulation is to be fastened to the concrete roof decking, and a fully adhered single ply membrane should be installed over the insulation. The current roof decking was installed in 1970 and it is recommended that the work be performed in the next year.

PRIORITY CLASS 2 PROJECTS	Solution Cost for Priority 2 Projects:	\$960
Necessary - Not Yet Critical	Two to Four Years	

EXTERIOR/INTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the interior and exterior of the building. Included in the cost is repairing cracked concrete, painting the precast concrete and caulking of any exterior penetrations. An epoxy paint is recommended on the interior precast concrete. It is recommended for this work to be performed in the next 2-3 years and for this project to be scheduled on a cyclical basis to maintain the integrity of the structure.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Site number: 9945

Project Index #:

Project Index #:

Construction Cost

Construction Cost

1065EXT1

\$960

1065EXT2

\$5,280

BUILDING INFORMATION:

Gross Area (square feet): Year Constructed:	48 1970
Exterior Finish 1:	100 # Painted Precast Conc
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # U
IBC Occupancy Type 2:	#
Construction Type:	Precast Concrete
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$130.00	Project Construction Cost per Square Foot:	\$5,280	Priority Class 1:
\$15,000	Total Facility Replacement Construction Cost:	\$960	Priority Class 2:
\$313	Facility Replacement Cost per Square Foot:	\$0	Priority Class 3:
42%	FCNI:	\$6,240	Grand Total:

State of Nevada / Conservation & Natural Resources **COMFORT STATION #1 - NORTH CAMPGROUND** SPWD Facility Condition Analysis - 1064 Survey Date: 4/13/2016

COMFORT STATION #1 - NORTH CAMPGROUND BUILDING REPORT

The Comfort Station #1 - North Campground is a wood framed structure on a concrete slab-on-grade foundation with a metal roofing system. There are Men's and Women's restrooms and a janitor's closet located in the facility.

PRIORITY CLASS 1 PROJECTS	5	Total Construction Cost for Priority 1 Projects:	\$72,500
Currently Critical	Immediate to Tw	o Years	

ADA PARKING AND PATH OF TRAVEL

The Americans with Disabilities Act (ADA) provides for accessibility to sites and services for people with physical limitations. A concrete parking area, passenger loading area and path of travel to the restroom are necessary to comply with ADA accessibility requirements. This project would provide for a concrete van accessible ADA parking and loading space and concrete walkway to the existing sidewalk. This will require regrading, placement of P.C. concrete, signage, striping and any other necessary upgrades. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009 and the most current version of the Americans With Disabilities Act Accessible Guidelines (ADAAG) were used as a reference for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

ADA RESTROOM UPGRADE

The Men's and Women's restrooms do not comply with the Americans with Disabilities Act (ADA) requirements. A complete retrofit is necessary. This project would provide funding to remodel one Men's and one Women's accessible restroom in the building. These items may include a new sink, toilet, hardware, mirrors, fixtures, flooring and paint. Nevada Revised Statutes (NRS) 338.180, International Building Code (IBC) 2012, ICC/ANSI A117.1 - 2009 and the most current version of the Americans with Disabilities Act Accessible Guidelines (ADAAG) were used as a reference for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

ADA SIGNAGE

Americans with Disabilities Act (ADA) regulations pertaining to building access has established building signage criteria for permanent spaces in buildings. The criteria includes: sign mounting heights and locations; character heights and proportions; raised and Braille characters/pictograms; and sign contrast and finish. The signage in this facility does not comply with these criteria. It is recommended that applicable signage be installed where required. Nevada Revised Statutes (NRS) 338.180, International Building Code (IBC) 2012, ICC/ANSI A117.1 - 2009 and the most current version of the Americans with Disabilities Act Accessible Guidelines (ADAAG) were used as references for this project. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Project Index #: 1064ADA3

Construction Cost \$2.500

Page 14 of 25

1064ADA1 \$30,000

1064ADA2

\$40.000

Project Index #:

Project Index #:

Construction Cost

PRIORITY CLASS 2 PROJECTS

Two to Four Years Necessary - Not Yet Critical

INTERIOR FINISHES

It is recommended that the interior walls and ceilings be painted at least once in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. Prior to painting, all surfaces should be repaired and prepped. An epoxy-based paint should be utilized in wet areas for durability.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding, priming, painting and caulking of the windows, flashing, fixtures and all other penetrations. It is recommended that the building be painted in the next 4-5 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

PRIORITY CLASS 3 PROJECTS **Total Construction Cost for Priority 3 Projects:** Four to Ten Years

Long-Term Needs

EXTERIOR FINISHES

BUILDING INFORMATION:

Gross Area (square feet):	433
Year Constructed:	1990
Exterior Finish 1:	100 # Painted Wood Siding
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # B
IBC Occupancy Type 2:	#
Construction Type:	Wood Framing
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$187.44	Project Construction Cost per Square Foot:	\$72,500	Priority Class 1:
\$173,000	Total Facility Replacement Construction Cost:	\$4,330	Priority Class 2:
\$400	Facility Replacement Cost per Square Foot:	\$4,330	Priority Class 3:
47%	FCNI:	\$81,160	Grand Total:

Project Index #: 1064INT1 \$4.330

Total Construction Cost for Priority 2 Projects: \$4,330

\$4,330

\$4,330

Construction Cost

Project Index #: 1064EXT2

Construction Cost

Page 15 of 25

State of Nevada / Conservation & Natural ResourcesCOMFORT STATION #2 - GROUP AREASPWD Facility Condition Analysis - 1063Survey Date:4/13/2016

COMFORT STATION #2 - GROUP AREA

BUILDING REPORT

The Comfort Station #2 - Group Area is a wood framed structure on a concrete slab-on-grade foundation with a metal roofing system. There are Men's and Women's restrooms and a janitor's closet located in the facility.

PRIORITY CLASS 1 PROJECT	5 Total Construction Cost for Priority 1 Projects:	\$72,500
Currently Critical	Immediate to Two Years	

ADA ACCESSIBLE PATH OF TRAVEL

The Americans with Disabilities Act (ADA) provides for accessibility to sites and services for people with physical limitations. A concrete parking area, passenger loading area and path of travel to the restrooms are necessary to comply with ADA accessibility requirements. This project would provide for a concrete, van accessible, ADA parking and loading space, and a concrete ADA walkway to the existing sidewalk. This will require re-grading, placement of P.C. concrete, signage, striping and any other necessary upgrades. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009 and the most current version of the Americans with Disabilities Act Accessible Guidelines (ADAAG) were used as references for this project. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

ADA RESTROOM UPGRADE

The Men's and Women's restrooms do not comply with the Americans with Disabilities Act (ADA) requirements. A complete retrofit is necessary. This project would provide funding remodel one Men's and one Women's accessible restroom in the building. Items may include a new sink, toilet, hardware, mirrors, fixtures, flooring and paint. Nevada Revised Statutes (NRS) 338.180, International Building Code (IBC) 2012, ICC/ANSI A117.1 - 2009 and the most current version of the Americans with Disabilities Act Accessible Guidelines (ADAAG) were used as references for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Project Index #:1063ADA3Construction Cost\$2,500

ADA SIGNAGE

Americans with Disabilities Act (ADA) regulations pertaining to building access has established building signage criteria for permanent spaces in buildings. The criteria includes: sign mounting heights and locations; character heights and proportions; raised and Braille characters/pictograms; and sign contrast and finish. The signage in this facility does not comply with these criteria. It is recommended that applicable signage be installed where required. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the most current version of the ADA Standards for Accessible Design were used as references for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Project Index #: 1063ADA1 Construction Cost \$30,000

Project Index #:1063ADA2Construction Cost\$40,000

03-Apr-17

Total Construction Cost for Priority 2 Projects:

Project Index #: 1063INT1 **Construction Cost** \$4.370

\$4,370

\$4,370

It is recommended that the interior walls and ceilings be painted at least once in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. Prior to painting, all surfaces should be repaired and prepped. An epoxy-based paint should be utilized in wet areas for durability.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

PRIORITY CLASS 3 PROJECTS **Total Construction Cost for Priority 3 Projects:** Four to Ten Years

Long-Term Needs

EXTERIOR FINISHES

Project Index #: 1063EXT2 **Construction Cost** \$4,370

Page 17 of 25

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding, priming, painting and caulking of the windows, flashing, fixtures and all other penetrations. It is recommended that the building be painted in the next 5-7 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

BUILDING INFORMATION:

Gross Area (square feet):	437
Year Constructed:	1990
Exterior Finish 1:	100 # Painted Wood Siding
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # B
IBC Occupancy Type 2:	#
Construction Type:	Wood Framing
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #
PROJECT CONSTRUCTION COST TOTALS SUMMA	RY:

\$185.90	Project Construction Cost per Square Foot:	\$72,500	Priority Class 1:
\$175,000	Total Facility Replacement Construction Cost:	\$4,370	Priority Class 2:
\$400	Facility Replacement Cost per Square Foot:	\$4,370	Priority Class 3:
46%	FCNI:	\$81,240	Grand Total:

INTERIOR FINISHES

PRIORITY CLASS 2 PROJECTS

Two to Four Years Necessary - Not Yet Critical

State of Nevada / Conservation & Natural Resources FISH CLEANING STATION - BOAT RAMP SPWD Facility Condition Analysis - 0510 Survey Date: 4/13/2016

FISH CLEANING STATION - BOAT RAMP BUILDING REPORT

The Fish Cleaning Station is a wood framed structure on a concrete slab-on-grade foundation with a metal roofing system. There is an ADA accessible parking space and route of travel to the cleaning area.

PRIORITY CLASS 1 PROJECT	S	Total Construction Cost for Priority 1 Projects:	\$12,500
Currently Critical	Immediate to Tw	vo Years	

ADA SIGNAGE

Americans with Disabilities Act (ADA) regulations pertaining to building access has established building signage criteria for permanent spaces in buildings. The criteria includes: sign mounting heights and locations; character heights and proportions; raised and Braille characters/pictograms; and sign contrast and finish. The signage in this facility does not comply with these criteria. It is recommended that applicable signage be installed where required. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the most current version of the ADA Standards for Accessible Design were used as references for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

FISH CLEANING STATION REPLACEMENT

The Fish Cleaning Station is original to the building, has reached the end of its expected life and does not meet the Americans with Disabilities Act (ADA) requirements. A complete replacement of the fish cleaning equipment is necessary. This project would provide for removal and disposal of the existing equipment and the replacement with a new accessible fish cleaning station equipped with a grinder and sprayer. Nevada Revised Statutes (NRS) 338.180, International Building Code (IBC) 2012, ICC/ANSI A117.1 - 2009 and the most current version of the Americans with Disabilities Act Accessible Guidelines (ADAAG) were used as references for this project. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

PRIORITY CLASS 2 PROJECTS	Total Construction Cost for Priority 2 Projects:	\$1,860
---------------------------	---	---------

Two to Four Years Necessary - Not Yet Critical

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding, priming, painting and caulking the flashing, fixtures and all other penetrations. It is recommended that the building be painted in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

INTERIOR FINISHES

It is recommended that the Fiberglass Reinforced Panels be power washed and re-caulked as needed. This project should be done at least once in the next 2-3 years and scheduled on a cyclical basis to maintain the integrity of the structure. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Project Index #:

Project Index #:

Construction Cost

Construction Cost

Project Index #:

Construction Cost

Construction Cost \$930

0510ADA1

0510ADA2

0510INT1

\$930

\$10,000

\$2,500

Project Index #: 0510EXT1

BUILDING INFORMATION:

Gross Area (square feet): Year Constructed:	
Exterior Finish 1:	100 # Painted Wood Siding
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # U
IBC Occupancy Type 2:	#
Construction Type:	Wood Framing
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$154.41	Project Construction Cost per Square Foot:	\$12,500	Priority Class 1:
\$23,000	Total Facility Replacement Construction Cost:	\$1,860	Priority Class 2:
\$250	Facility Replacement Cost per Square Foot:	\$0	Priority Class 3:
62%	FCNI:	\$14,360	Grand Total:

State of Nevada / Conservation & Natural Resources **COMFORT STATION #3 - BOAT RAMP** SPWD Facility Condition Analysis - 0509 Survey Date: 4/13/2016

COMFORT STATION #3 - BOAT RAMP BUILDING REPORT

The Comfort Station #3 is a wood framed structure on a concrete slab-on-grade foundation with a metal roofing system. There are Men's and Women's restrooms and a janitor's closet located in the facility. There is an adjacent ADA accessible parking space and route of travel to the restroom.

PRIORITY CLASS 1 PROJECTS	5 Total Construction Cost for Priority 1 Projects:	\$6,500
Currently Critical	Immediate to Two Years	

ADA SIGNAGE

Americans with Disabilities Act (ADA) regulations pertaining to building access has established building signage criteria for permanent spaces in buildings. The criteria includes: sign mounting heights and locations; character heights and proportions; raised and Braille characters/pictograms; and sign contrast and finish. The signage in this facility does not comply with these criteria. It is recommended that applicable signage be installed where required. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the most current version of the ADA Standards for Accessible Design were used as references for this project.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

DUAL LEVEL DRINKING FOUNTAIN INSTALLATION

There is a water fountain mounted on the exterior of this building. The 2012 International Building Code (IBC) Section 1109.5 states where a water fountain is provided, at least half should be accessible for people who use a wheelchair. This project would provide funding for the purchase and installation of a ADA new accessible fixed high/ low drinking fountain.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

PRIORITY CLASS 2 PROJECTS

Two to Four Years Necessary - Not Yet Critical

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost are cleaning and sealing the brick masonry and caulking of the flashing, fixtures and all other penetrations. It is recommended that the building be sealed and caulked in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

INTERIOR FINISHES

It is recommended that the interior walls and ceilings be painted at least once in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. Prior to painting, all surfaces should be repaired and prepped. An epoxy-based paint should be utilized in wet areas for durability.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

03-Apr-17

Project Index #:

Construction Cost

Project Index #: 0509ADA1 **Construction Cost** \$4,000

Project Index #: 0509EXT1

Total Construction Cost for Priority 2 Projects:

Construction Cost \$2,500

0509ADA2

\$2,500

\$17,000

0509INT1

\$2.500

Site number: 9945

Project Index #:

photovoltaic system including solar panels, deep cycle solar batteries and all associated electrical boxes and hardware to connect it to the furnace and water heater. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Four to Ten Years

WIRING CLEANUP

The wiring inside the Comfort Station #3 - Boat Ramp is disorganized and not in proper electrical boxes, particularly the old main service wires. This creates a safety issue during repairs or upgrades. This project would provide for organization, proper labeling and for the wiring to be placed in electrical boxes per National Electrical Code (NEC) 2011.

There is a propane-fired furnace and a propane-fired water heater in the building that are not connected to power. The

existing photovoltaic system only has enough power for the lighting and it is recommended to install a second photovoltaic system to provide additional power. This project would provide for the purchase and installation of a

PRIORITY CLASS 3 PROJECTS

PHOTOVOLTAIC SYSTEM INSTALLATION

Long-Term Needs

WATER HEATER REPLACEMENT

There is an on-demand propane-fired water heater in the building. The average life span of a water heater is 8-10 years. With the passage of time and constant use, this unit is showing signs of wear and should be scheduled for replacement in the next 4-5 years. It is recommended that a new on-demand propane-fired water heater be installed. Removal and disposal of the existing equipment is included in the estimate.

BUILDING INFORMATION:

Gross Area (square feet):	250
Year Constructed:	1994
Exterior Finish 1:	100 # Brick Masonry
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # B
IBC Occupancy Type 2:	#
Construction Type:	Brick Masonry & Wood
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

\$104.00	Project Construction Cost per Square Foot:	\$6,500	Priority Class 1:
\$100,000	Total Facility Replacement Construction Cost:	\$17,000	Priority Class 2:
\$400	Facility Replacement Cost per Square Foot:	\$2,500	Priority Class 3:
26%	FCNI:	\$26,000	Grand Total:

Project Index #:0509ENR1Construction Cost\$10,000

Project Index #: 0509ELE2 Construction Cost \$2,000

Project Index #:

Construction Cost

0509PLM1

\$2,500

Total Construction Cost for Priority 3 Projects: \$2,500

State of Nevada / Conservation & Natural Resources PARK OFFICE SPWD Facility Condition Analysis - 0508 Survey Date: 4/13/2016

PARK OFFICE

BUILDING REPORT

The Park Office is a wood framed structure on a concrete slab-on-grade foundation with metal siding and a metal roof. It is located in the park office complex below the dam.

PRIORITY CLASS 1 PROJECTS	5 Total Construction Cost for Priority 1 Projects:	\$33,000
Currently Critical	Immediate to Two Years	

ADA DOOR & THRESHOLD REPLACEMENT

The existing exterior entrance door and threshold to the Park Office is not accessible. This project would provide for a new accessible door and threshold assembly including removal of the existing door assembly and installation of the new accessible door assembly. ADA compliant signage is also included in this project. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the most current version of the ADA Standards For Accessible Design were used as a reference for this project.

This project or a portion there of was previously recommended in the FCA report dated 09/27/2005. It has been amended accordingly to reflect conditions observed during the most recent survey date of 06/29/2016.

ADA PARKING SPACE

The Americans with Disabilities Act (ADA) provides for accessibility to sites and services for people with physical limitations. A concrete parking area and passenger loading area are necessary to comply with ADA requirements. This project would provide for a concrete, van accessible, ADA parking and loading space and a walkway. This will require regrading, installing P.C. concrete, striping, signage and any other necessary upgrades. The 2012 International Building Code (IBC), ICC/ANSI A117.1 - 2009, Nevada Revised Statutes (NRS) 338.180 and the most current version of the ADA Standards for Accessible Design were used as references for this project.

ADA UPGRADES

Section 4.13.9 of the Americans with Disabilities Act Accessibility Guidelines (ADAAG) states that handles, pulls, latches, locks and other operating devices on accessible doors shall have a shape that is easy to grasp with one hand and does not require tight grasping, tight pinching, or twisting of the wrist to operate. Lever-operated mechanisms, push-type mechanisms, and U-shaped handles are acceptable designs. It is recommended that proper lever hardware be installed in this building to meet these requirements.

PRIORITY CLASS 2 PROJECTS

Two to Four Years Necessary - Not Yet Critical

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding and painting the wood trim and caulking and sealing of the windows, flashing, fixtures and all other penetrations. It is recommended that the building be caulked and sealed in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure.

This project or a portion there of was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Project Index #:

Project Index #:

Construction Cost

Construction Cost

Project Index #: 0508ADA3 **Construction Cost** \$500

Project Index #: 0508EXT1

Total Construction Cost for Priority 2 Projects:

Construction Cost \$1,470

Page 22 of 25

0508ADA1

0508ADA2

\$2,500

\$5,940

\$30,000

Site number: 9945

of the existing windows is included in this estimate.

Exterior r mish 2.	n
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # B
IBC Occupancy Type 2:	#
Construction Type:	Wood Framing
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

#

Metal Siding

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

Priority Class 1:	\$33,000	Project Construction Cost per Square Foot:	\$264.90
Priority Class 2:	\$5,940	Total Facility Replacement Construction Cost:	\$29,000
Priority Class 3:	\$0	Facility Replacement Cost per Square Foot:	\$200
Grand Total:	\$38,940	FCNI:	134%

INTERIOR FINISHES

It is recommended that the interior walls and ceilings be painted at least once in the next 2-3 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. Prior to painting, all surfaces should be repaired and prepped.

This project or a portion there of was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

The windows are original, double pane construction with metal frames. These older windows are drafty and not energy efficient. This project recommends replacing the windows with dual pane, higher efficiency units. Removal and disposal

Gross Area (square feet): 147

Exterior Finish 2:

Year Constructed: 1986 Exterior Finish 1: 100 #

WINDOW REPLACEMENT

BUILDING INFORMATION:

Project Index #: 0508INT1 Construction Cost \$1,470

0508EXT2

\$3,000

Project Index #:

State of Nevada / Conservation & Natural Resources PARK RESIDENCE SPWD Facility Condition Analysis - 0507 Survey Date: 4/13/2016

PARK RESIDENCE

BUILDING REPORT

The Park Residence is a wood framed structure on a concrete slab-on-grade foundation with a metal roofing system.

PRIORITY CLASS 1 PROJECTS	Total Construction Cost for Priority 1 Projects:	\$2,500
Currently Critical	Immediate to Two Years	

WATER HEATER REPLACEMENT

There is a 74 gallon propane water heater in the building. The average lifespan of a water heater is eight to ten years. This unit was installed in 2004. It is recommended that a new propane water heater, seismic straps, braided steel hose, expansion tank, ball valves, new flex gas line and a pan be installed. The removal and disposal of the existing equipment is included in this estimate.

PRIORITY CLASS 3 PROJECTS	Total Construction Cost for Priority 3 Projects:	\$31,600
Long-Term Needs	Four to Ten Years	

EXTERIOR FINISHES

It is important to maintain the finish, weather resistance and appearance of the building. This project would provide funding to protect the exterior of the building excluding the roof. Included in the cost is sanding, priming, painting and caulking of the windows, flashing, fixtures and all other penetrations. It is recommended that the building be painted in the next 4-5 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

INTERIOR FINISHES

It is recommended that the interior walls and ceilings be painted at least once in the next 4-5 years and that this project be scheduled on a cyclical basis to maintain the integrity of the structure. Prior to painting, all surfaces should be repaired and prepped. An epoxy-based paint should be utilized in wet areas for durability.

This project or a portion thereof was previously recommended in the FCA report dated 09/22/2010. It has been amended accordingly to reflect conditions observed during the most recent survey date of 04/13/2016.

Page 24 of 25

Project Index #: 0507INT1 **Construction Cost** \$15,800

Construction Cost \$2,500

Project Index #:

Project Index #:

Construction Cost

0507PLM1

0507EXT1

\$15.800

Site number: 9945

BUILDING INFORMATION:

Gross Area (square feet):	1,580
Year Constructed:	1991
Exterior Finish 1:	100 # Painted Wood Siding
Exterior Finish 2:	#
Number of Levels (Floors):	1 Basement? No
IBC Occupancy Type 1:	100 # R-3
IBC Occupancy Type 2:	#
Construction Type:	Wood Framing
IBC Construction Type:	V-B
Percent Fire Suppressed:	0 #

PROJECT CONSTRUCTION COST TOTALS SUMMARY:

Priority Class 1:	\$2,500	Project Construction Cost per Square Foot:	\$21.58
Priority Class 2:	\$0	Total Facility Replacement Construction Cost:	\$474,000
Priority Class 3:	\$31,600	Facility Replacement Cost per Square Foot:	\$300
Grand Total:	\$34,100	FCNI:	7%

NOTES:

The deficiencies outlined in this report were noted from a visual survey. The costs do not represent the cost of a complete facility renovation or maintenance needs. Recommended projects do not include telecommunications, furniture, window treatment, space change, program issues, relocation, swing space, or costs that could not be identified or determined from the survey and available building

Individual projects and costs noted herein may be impacted by new construction materials or methods, agency projects, and pending or proposed Capital Improvement Projects (CIP).

This report was created under the authority found in NRS 341.128 by the State Public Works Division and should be utilized as a planning level document.

REPORT DEVELOPMENT:

State Public Works Division	515 E. Musser Street, Suite 102	(775) 684-4141 voice
Facilities Condition Analysis	Carson City, Nevada 89701-4263	(775) 684-4142 facsimile




Echo Canyon State Park Site - Site #9945 Description: New campground with shade ramadas, utility hook-ups and a comfort station.



ADA CXT Comfort Station #1 – Building #3729 Description: Exterior finishes.



Park Residence Metal Shed #1 - Building #3727 Description: Safety cabinet needed.



Park Office Storage Shed #2 - Building #3082 Description: Roofing replacement needed.



Park Office Storage Shed - Building #1101 Description: Exterior finishes needed.



Fish Cleaning Station – Boat Ramp #0510 Description: ADA Fish Cleaning Station replacement needed.



Comfort Station #3 - Building #0509 Description: Wiring cleanup needed.



Park Office - Building #0508 Description: ADA upgrades needed.



Park Residence - Building #0507 Description: Exterior finishes needed.



Comfort Station #1 – North Campground #1064 Description: ADA parking and path of travel needed.



Park Well House - Building #1065 Description: Concrete patch/ roofing needed.